FEBRUARY 6, 2020 HINCKLEY NEWS **9**

February 2019







Rooms are framed, cement is poured for the walking track and progress on the gym continues.

June 2019





August 2019

The original section of the building also received a face lift.

April 2019



Painting begins before the floor is laid to prevent any damage to the floors.

May 2019



Basketball floor construction began on Wednesday, May 1. The floor consists of three layers. Layer number one is sleepers, two by three-inch strips of wood, which are spaced and nailed to the cement. This provides a solid base for the maple flooring. Next comes the plywood, nailed to the strips of wood. Finally, the grade A2 maple flooring is nailed to the sub floor at a right angle to the sleepers and plywood. Every four feet, there is a 1/16 of an inch space left for expansion and contraction of the wood. Through the entire perimeter of the floor, there is a two-inch space left for the same reason.

September 2019





The brand new fitness center and walking track are open for public use with membership. Welia Health committed to investing \$250,000 for the fitness center area in exchange for naming rights.



The new larger Early Childhood was much needed.